

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<p><u>PROPOSED ADDITIONAL MARKET SHEDS AT MITUNGUU MARKET</u></p> <p><u>ELEMENT NO. 1</u></p> <p><u>GATES</u></p> <p><u>Access Gate</u></p> <p>Supply and fix 5000 x 2100mm high double leaf gate comprising of 2 No.2500 x 2100mm high equal epenable leaves built with 50 x 50mm RHS stiles, top and bottom rails infilled with 8x25mm mild steel flats and 25x25mm RHS members all welded to form pattern on each leaf complete with 50x50mm RHS frame, 6No. pin hinges complete with all associated ironmongery.</p>	2	NO		
A.					
	<p><u>Pedestrian Gate</u></p> <p>Supply and fix 2000 x 2100mm high single leaf pedestrian gate built with 50 x 50X3mm RHS stiles, top and bottom rails infilled with 8x25mm mild steel flats and 25x25X3mm RHS members all welded to form pattern, complete with 50x50mm RHS frame, 3No. pin hinges complete with all associated ironmongery</p>	1	NO		
B					
	<p><u>Painting and decoration</u></p> <p>Prepare and apply two undercoats and one coat of gloss oil paint to surface of metal</p>	50	SM		
C					
	<p><u>ELEMENT NO. 2</u></p> <p><u>MASONRY WALL</u></p> <p><u>Machine cut stone or other equal and approved walling in Cement : sand (1:4) mortar :-</u></p>				
A	<p>Construct a 200 mm thick boundary wall, neat horizontal and vertical key pointing internally and externally to block off existing opening, including excavation and backfilling for foundations, demolition of existing wall to create toothing and making good disturbed surfaces</p>	22	SM		
	<p><u>ELEMENT NO. 3</u></p> <p><u>RELOCATION OF GARBAGE RECEPTACLE</u></p>				
A	<p>Carefully demolish existing 200mm thick masonry structure, overall size 2500x2500x3000mm high ncluding a timber roof structure and a IT5 sheets roof covering and ramp, and store materials on site for reuse as directed by the architect (Approx 30 sm)</p>		ITEM		
B	<p>Allow for labour and materials for construction garbage receptacle overall size 2500 x 2500 x 2800mm high</p>		ITEM		
	Total carried to collection				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
A	<p><u>ELEMENT NO. 4</u> <u>REVENUE COLLECTION POINT</u></p> <p>Allow for construction of a revenue collection point consisting of a 200mm thick masonry walling approx. 1200mm high and mild steel mild steel grille comprising 50 x 50x2mm rolled hollow section frame all round and cross bracing of 100 x 50 mm RHS top, middle and bottom rail. 50x 25 mm vertical support bars at 150 mm centre spacing including all hinges, fixing lugs and painting.</p>		ITEM		
	Total carried to collection				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>ROOFING SHEDS</u>				
	<u>ELEMENT NO. 5</u>				
	<u>SUBSTRUCTURE (ALL PROVISIONAL) :-</u>				
A	Excavate pits in normal soil for column bases depth not	78	CM		
B	Load, cart away and spread extra excavation material on site as directed by the Architect.	8	CM		
C	Return, fill and ram selected excavated materials to sides of pits.	70	CM		
	<u>Filling</u>				
D	50 mm thick murrum or other equal and approved	774	SM		
	<u>Plain concrete (1:4:8) as described in :-</u>				
A.	50 mm thick under strip foundation	180	SM		
B	Column bases	52	SM		
	<u>Reinforced concrete 1:2:4 as described in :-</u>				
C	Column bases	18	CM		
D	Column	3	CM		
	<u>Sawn formwork as described to :-</u>				
E	Column bases	73	SM		
F	Column	69	SM		
	<u>High Tensile Reinforcement Bars to B. S. 4461 including cutting, bending and all necessary spacer blocks : (Provisional):-</u>				
G	12 mm diameter	336	KG		
H	10 mm diameter	756	KG		
I	8 mm diameter	588	KG		
	Total carried to collection				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>Water disposal</u>				
A.	Allow for keeping all excavation clear of surface and running water		ITEM		
	<u>Plunking and Strutting</u>				
B.	Allow for plunking and strutting to sides of all excavation		ITEM		
	Total carried to collection				
	<u>COLLECTION</u>				
	Carried forward from page 1				
	Brought down from above				
	<u>TOTAL CARRIED TO SUMMARY</u>				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>ELEMENT NO. 6</u>				
	<u>STRUCTURAL STEEL (Welded & Bolted joints)</u>				
	<u>The following in structural columns:-</u>				
A.	Supply and fix 100 mm diameter x 3 mm thick circular hollow section secured onto the columns	234	LM		
	<u>ROOF</u>				
A	50x50x3mm RHS truss rafters joined by 6mm welds and bolted to steel tubes.	281	LM		
B	Ditto but truss struts and braces	384	LM		
C	75 x 50 mm x 2 mm thick (14 gauge) Zed Purlins welded/riveted/ and or bolted to steel tubes.	384	LM		
D	300x75x4mm thick mild steel anchor plate to engineer's detail	52	NO		
	<u>Roof Covering :-</u>				
	<u>Supply and fix gauge 28 IT5 roofing sheets or other equal and approved roof covering as described in :-</u>				
E	Roof coverings	527	SM		
F	Ditto ; translucent sheets	53	SM		
	<u>Rainwater Disposal:-</u>				
	<u>28 Gauge SWG galvanized mild steel rainwater goods with lapped, rivetted and soldered joints or seams including all labours :-</u>				
G	150 x 200 mm rectangular boxed eaves gutter including fixing clamps at 600 mm centre.	76	LM		
H	100 mm diameter rainwater downpipe imbedded to walls or boxed in walls and all necessary clamping.	42	LM		
I	Extra over ditto for swan neck	14	NO		
J	Ditto for shoe	14	NO		
	<u>Touch up primer prepare and apply three coats gloss oil paint on metal surfaces as described in :-</u>				
K	Surfaces of gutter 200 -300 mm girth	118	LM		
	<u>TOTAL CARRIED TO SUMMARY</u>				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	SUMMARY				
1	Carried forward from page 1				
2	Carried forward from page 2				
3	Carried forward from page 4				
4	Carried forward from page 5				
	TOTAL FOR ROOFING SHED CARRIED TO GRAND SUMMARY				

PROVISIONAL AND PRIME COST SUMS

GRAND SUMMARY

BILL NO.	DESCRIPTION	PAGE	CONTRACT OR SHS. CTS.	OFFICIAL SHS. CTS.
	<u>PROPOSED ADDITIONAL MARKET SHEDS AT MITUNGUU MARKET</u>			
	<u>GRAND SUMMARY</u>			
1	Particular Preliminaries			
2	General Preliminaries			
3	Trade Preambles and Pricing Notes			
4	Builder's Work : • ROOF SHEDS			
5	P. C. and Provisional Sums	PCPS/1		300,000.00
	TOTAL ESTIMATE FOR BUILDER'S WORKS CARRIED TO FORM OF TENDER			

CONTRACTOR

.....

Signature

Address

Official stamp.....

EMPLOYER

Name of Employer

Signature

Address

Official stamp.....

GS/1