

ITEM	DESCRIPTION	QTY	UNIT	RATE	SHS.
<u>PROPOSED CONSTRUCTION OF BOUNDARY WALL AT KUNATI MARKET</u>					
<u>BOUNDARY WALL</u>					
<u>ELEMENT NO. 1</u>					
<u>SUBSTRUCTURE (ALL PROVISIONAL) :-</u>					
A	Excavate trenches in normal soil for strip footing not exceeding 1.50 M deep from the ground level.	297	CM		
B	Excavate trenches in normal soil for column bases not exceeding 1.50 M deep from the ground level.	238	CM		
C	Load, cart away and spread extra excavation material on sited as directed by the Architect.	47	CM		
<u>Filling</u>					
D	Return fill and rum selected excavated material to sides of foundation walling.	488	CM		
<u>Plain concrete (1:4:8) as described in :-</u>					
E	50 mm thick column bases	158	SM		
F	50 mm thick foundation footing	198	SM		
<u>Reinforced concrete 1:2:4 as described in :-</u>					
G	Column bases	40	CM		
H	Columns	7	CM		
I	Strip footing	50	CM		
<u>Sawn formwork as described to :-</u>					
J	Sides of columns	121	SM		
K	Edges of column bases 150 - 225 mm girth	211	LM		
L	Sides of columns	176	SM		
	Sides of strip footing	165	SM		
<u>WALLING</u>					
<u>Machine cut stone or other equal and approved walling in Cement : sand (1:4) mortar :-</u>					
M	200 mm thick boundary wall including neat horizontal and vertical key pointing internally and externally	396	SM		
Total carried to collection					

ITEM	DESCRIPTION	QTY	UNIT	RATE	SHS.
	<u>High Tensile Reinforcement Bars to B. S. 4461 including cutting, bending and all necessary spacer blocks : (Provisional) [100 Kg/Cm] :-</u>				
A	12 mm diameter	2910	KG		
B	10 mm diameter	4365	KG		
C	8 mm diameter	1940	KG		
	<u>Mild Steel Reinforcement Bars to B. S. 4449 including cutting, bending and all necessary spacer blocks : (Provisional) :-</u>				
D	8 mm diameter	485	KG		
	Total carried to collection				
	<u>COLLECTION</u>				
	Carried forward from page 2				
	Brought down from above				
	Total carried to Summary				

ITEM	DESCRIPTION	QTY	UNIT	RATE	SHS.
	<u>ELEMENT NO. 2</u>				
	<u>R. C. SUPERSTRUCTURE :-</u>				
	<u>Reinforced concrete (1:2:4) as described to :-</u>				
A.	Columns	14	CM		
	<u>High Tensile Reinforcement Bars to B. S. 4461 including cutting, bending and all necessary spacer blocks : (Provisional) :-</u>				
B.	12 mm diameter	420	KG		
C	8 mm ditto	630	KG		
D.	8 mm ditto	350	KG		
	<u>Sawn formwork as described to :-</u>				
E	Sides of columns	277	SM		
	Total carried to Summary				

ITEM	DESCRIPTION	QTY	UNIT	RATE	SHS.
	<u>ELEMENT NO. 3</u>				
	<u>WALLING</u>				
	<u>Machine cut stone or other equal and approved walling in Cement : sand (1:4) mortar :-</u>				
A.	200 mm thick boundary wall including placing poe lamps after every 3meters, neat horizontal and vertical key pointing internally and externally	673	SM		
	<u>Precast Concrete</u>				
B.	275 x 50 mm thick pre-cast concrete coping bedded and jointed in cement : sand (1:4) mortar.	306	LM		
C.	350 x 350 x 50 mm thick column ditto	110	NO		
D	Excavate 5000x1500x12000mm deep external pit latrine, cover it with reinforced concrete slab overall size 6000X2000, and put up 2700mm high masonry structure roofed with mono pitch IT5 roof cover laid on timber trusses. Walls shall be finished with plaster and tiles as specified by the architect.	2	item		
	Total carried to Summary				

ITEM	DESCRIPTION	QTY	UNIT	RATE	SHS.
	<u>SUMMARY</u>				
1	Substructure				
2	Reinforced Concrete Superstructure				
3	Walling				
4	Gates				
	TOTAL FOR BOUNDARY WALL CARRIED TO GRAND SUMMARY				

PROVISIONAL AND PRIME COST SUMS

GRAND SUMMARY

BILL NO.	DESCRIPTION	PAGE	CONTRACTOR SHS. CTS.	OFFICIAL SHS. CTS.	CTS.
	<p><u>PROPOSED CONSTRUCTION OF BOUNDARY WALL AT KUNATI MARKET</u></p> <p><u>GRAND SUMMARY</u></p> <p>1 Particular Preliminaries</p> <p>2 General Preliminaries</p> <p>3 Trade Preambles and Pricing Notes</p> <p>4 Builder's Work : BOUNDARY WALL</p> <ul style="list-style-type: none"> • BOUNDARY WALL • PC & PROVISIONAL SUMS <p><i>SUB TOTAL 1</i></p> <p><i>ADD 16% VAT</i></p> <p>TOTAL COST OF THE WORKS CARRIED TO FORM OF TENDER</p>	PCPS/1			

CONTRACTOR

.....

Signature

Address

Official stamp

EMPLOYER

Name of Employer

Signature

Address

GS/1