

PROPOSED FLOORING OF NKUBU SHOE TRADERS MARKET IN NKUENE WARD

Item No	Description	Unit	Qty	Rate	Amount
	<u>PROPOSED FLOORING OF NKUBU SHOE TRADERS MARKET IN NKUENE WARD</u>				
	Bill No. 1				
	Sub-structures				
	Provisional				
	Excavations				
A	Excavate in site soils to reduce levels, average depth 450mm	M ³	577		
B	Extra over excavating in rock.	M ³	173		
	Planking & strutting				
C	Allow for maintainign and supporting sides of axcavations and for keeping the same from fallen material	Item			
D	Allow for keeping excavations free of water and mud by pumping,bailing or other approved means.	Item			
	Filling/Disposal				
E	Return/fill and ram selected inported murrum material.	M ³	58		
	Carried to Collection				

PROPOSED FLOORING OF NKUBU SHOE TRADERS MARKET IN NKUENE WARD

Item No	Description	Unit	Qty	Rate	Amount
F	Load, wheel and deposit surplus excavated material where directed by architect on site not exceeding 50 metres away.	M ³	202		
G	Hardcore filling 300mm thick under floors compacted in 150mm layers	M ²	577		
H	50mm thick quarry dust blinding to surfaces of hardcore.	M ²	577		
	Anti-termite treatment				
I	Chemical antitermite treatment executed complete by an approved specialist under a ten (10) year guarantee to surfaces of hardcore.	M ²	577		
	Damp proof membrane				
J	500gauge polythene or other equal and approved damp proof membrane laid under surface bed with 300mm side and end laps (measured nett-allow for laps)	M ²	577		
	Concrete Work				
	Concrete 1:3:6 as described in				
K	50mm thick blinding	M ²	577		
	Reinforced concrete 1:2:4 as described in				
L	150mm thick surface bed.	M ³	577		
	Reinforcement				
	Fabric to BS 44873 and setting in concrete with 300mm side and end laps (measured net tallow for laps)				
A	Fabric mesh ref:A98 weighing 0.54 Kg per square metre in floor bed and ramps.	M ²	577		
	Sawn Formwork to;				
G	Edges of ground floor slab over 75mm but not exceeding 150mm high.	M	148		
	Sub - Total				
	Collection Carried from page 1 Carried from above				
	Total for Substructure				

PROPOSED FLOORING OF NKUBU SHOE TRADERS MARKET IN NKUENE WARD

Item No	Description	Unit	Qty	Rate	Amount
A	Floor finishes Insitu cement and sand (1:4) screeded beds,with wood trowelled finish, on concrete				
	25mm thick to laid to falls	M ²	577		
	Total for Finishes				

PROPOSED FLOORING OF NKUBU SHOE TRADERS MARKET IN NKUENE WARD

Item No	Description	Unit	Qty	Rate	Amount
Summary					
1	Substructures				
2	Finishes				
Total Carried to Grand Summary					

PROPOSED FLOORING OF NKUBU SHOE TRADERS MARKET IN NKUENE WARD

ITEM	DESCRIPTION	QTY	UNIT	RATE	SHS.	CTS.
	<u>PROPOSED FLOORING OF NKUBU SHOE TRADERS MARKET IN NKUENE WARD</u>					
	<u>P.C. AND PROVISIONAL SUMS</u>					
	<u>Project Management</u>					
A.	Allow a provisional sum of Kenya Shillings One Hudrend Thousand (Kshs 100,000.00) for Project management		SUM		100,000	00
	<u>Contingency</u>					
B	Allow a provisional sum of Kenya Shillings Two Hudrend Thousand (Kshs 200,000.00) for Contigencies		SUM		200,000	00
	TOTAL FOR P.C. AND PROVISIONAL SUMS CARRIED TO GRAND SUMMARY				300,000	00
	PCPS/1					

PROPOSED FLOORING OF NKUBU SHOE TRADERS MARKET IN NKUENE WARD

BILL NO.	DESCRIPTION	PAGE	CONTRACTOR SHS. CTS.	OFFICIAL SHS. CTS.	CTS.
	<p><u>PROPOSED FLOORING OF NKUBU SHOE TRADERS MARKET IN NKUENE WARD</u></p> <p><u>GRAND SUMMARY</u></p> <p>1 Particular Preliminaries</p> <p>2 General Preliminaries</p> <p>3 Trade Preambles and Pricing Notes</p> <p>4 Builder's Work :</p> <ul style="list-style-type: none"> • BUILDERS WORKS <p>5 P. C. and Provisional Sums</p> <p>ADD 16% VAT</p> <p align="center">TOTAL FOR BUILDER'S WORKS [VAT INCLUSIVE] CARRIED TO FORM OF TENDER</p>				
		PCPS/1		300,000	00